



Industrie Service

**Choose certainty.
Add value.**

Validation Report

AGCERT INTERNATIONAL LIMITED, IRELAND

Validation of the AWMS Methane Recovery Project BR07- S -31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Ca- tarina, Brazil

Report No. 949531 rev. 0

June 03, 2007

TÜV SÜD Industrie Service GmbH
Carbon Management Service
Westendstr. 199 - 80686 Munich – GERMANY

Report No.	Date of first issue	Revision No.	Date of this revision	Certificate No.
949531	June 03, 2007.	0		---
Subject:		Validation of a CDM Project		
Executing Operational Unit:		TÜV SÜD Industrie Service GmbH Carbon Management Service Westendstr. 199 - 80686 Munich Federal Republic of Germany		
Contact:		www.tuev-sued.de		
Client:		AgCert International PLC, Ireland Sandyford Business Park The Apex Building Dublin 18, Ireland		
Contract approved by:		Werner Betzenbichler		
Report Title:		Validation of the AWMS Methane Recovery Project BR07-S–31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil		
Number of pages		21 (excluding annexes and cover page)		
Summary: The Certification Body "Climate and Energy" has been ordered by AgCert International PLC, Ireland (AgCert International) to perform a validation of the above mentioned project. In summary, it is TÜV SÜD's opinion that the project "AWMS Methane Recovery Project BR07-S–31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil", as described in the revised project design document of May 23, 2007 meets all relevant UNFCCC requirements for the CDM, set by the Kyoto Protocol, the Marrakech Accords and relevant guidance by the CDM Executive Board and that the project furthermore meets all relevant host country criteria and correctly applies the baseline and monitoring methodology Type III, Other Project Activities, Category III.D., Methane recovery in agricultural and agro industrial activities for small-scale projects. Prior to the submission of this validation report to the CDM Executive Board, TÜV SÜD will have to receive the written approval of the DNA of involved parties, including confirmation by the DNA of Brazil that the project assists in achieving sustainable development. Hence, TÜV SÜD will recommend the project for registration as CDM project activity by the CDM Executive Board. Additionally the assessment team reviewed the estimation of the projected emission reductions. TÜV SÜD confirms that the indicated amount of emission reductions of 114,788 tonnes CO _{2e} over a renewable crediting period of seven years, resulting in a calculated annual average of 16,398 tonnes CO _{2e} represents a reasonable estimation using the assumptions given by the project documents.				
Work carried out by:	Markus Knödseder Johann Thaler Sandro Marostica	Internal Quality Control by:	Javier Castro	

Abbreviations

AgCert Brazil	AgCert Do Brasil Solucoes Ambientais Ltda.
AgCert International	AgCert International PLC, Ireland
AWMS	Animal Waste Management Systems
CAR	Corrective Action Request
CDM	Clean Development Mechanism
CER	Certified Emission Reduction
CR	Clarification Request
DOE	Designated Operational Entity
EIA / EA	Environmental Impact Assessment / Environmental Assessment
ER	Emission reduction
GHG	Greenhouse gas(es)
KP	Kyoto Protocol
MP	Monitoring Plan
SSC	Small Scale Project
PDD	Project Design Document
TÜV SÜD	TÜV SÜD Industrie Service GmbH
UNFCCC	United Nations Framework Convention on Climate Change
VVM	Validation and Verification Manual

Table of Contents	Page
1 INTRODUCTION	4
1.1 Objective	4
1.2 Scope	4
1.3 GHG Project Description	5
2 METHODOLOGY	6
2.1 Review of Documents	7
2.2 Follow-up Interviews	7
2.3 Resolution of Clarification and Corrective Action Requests	8
3 VALIDATION FINDINGS	9
3.1 General Description of Project Activity	9
3.2 Baseline Methodology	12
3.3 Duration of the Project / Crediting Period	14
3.4 Monitoring Plan	15
3.5 Calculation of GHG Emissions by Source	16
3.6 Environmental Impacts	17
3.7 Comments by Local Stakeholders	18
4 COMMENTS BY PARTIES, STAKEHOLDERS AND NGOS	19
5 VALIDATION OPINION	20

Annex 1: Validation Protocol

Annex 2: Information Reference List

1 INTRODUCTION

1.1 Objective

AgCert International PLC, Ireland (AgCert International) has commissioned TÜV SÜD Industrie Service GmbH (TÜV SÜD) to validate the AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil.

The validation serves as design verification and is a requirement of all CDM projects. The purpose of a validation is to have an independent third party assess of the project design. In particular, the project's baseline, the monitoring plan (MP), and the project's compliance with relevant UNFCCC and host country criteria are validated in order to confirm that the project design as documented is sound and reasonable and meets the stated requirements and identified criteria. Validation is a requirement for all CDM projects and is seen as necessary to provide assurance to stakeholders of the quality of the project and its intended generation of certified emission reductions (CERs).

UNFCCC criteria refer to the Kyoto Protocol criteria and the CDM rules and modalities as agreed in the Bonn Agreement and the Marrakech Accords.

1.2 Scope

The validation scope is defined as an independent and objective review of the project design document, the project's baseline study and monitoring plan and other relevant documents. The information in these documents is reviewed against Kyoto Protocol requirements, UNFCCC rules and associated interpretations. TÜV SÜD has, based on the recommendations in the Validation and Verification Manual employed a risk-based approach in the validation, focusing on the identification of significant risks for project implementation and the generation of CERs.

The audit team has been provided with the first PDD-version in January 2007. Based on this documentation a document review and a fact finding mission in form of an on site audit has taken place. The demanded additional information is addressed in annex 1. Requested information was given and the PDD was updated accordingly. That final PDD version 3 was issued on 23.05.2007 and serves as the basis for the final assessment presented herewith. The changes were not significant as only some information was added and adapted to the final PDD, thus the global stakeholder process was not repeated.

Studying the existing project documentation, it was obvious that the competence and capability of the validation team has to cover at least the following aspects:

- Knowledge of Kyoto Protocol and the Marrakech Accords
- Environmental and Social Impact Assessment
- Skills in environmental auditing (ISO 14000, EMAS)
- Quality assurance
- Agricultural operations especially regarding manure management

- Technical aspects of gas flaring and bio digester operation
- Monitoring concepts
- Political, economical and technical random conditions in host country

According to these requirements TÜV SÜD has assembled a project team in accordance with the appointment rules of the TÜV certification body “climate and energy”:

Markus Knödlseider is an auditor for climate change projects and GHG emission inventories at the department “Carbon Management Service” in the head office of TÜV SÜD in Munich. He has been involved in the topic of environmental auditing, baselining, monitoring and verification due to the requirements of the Kyoto Protocol since Oct. 2001. His main focus lies on renewable energies.

Johann Thaler graduated as Master of environmental Economy at the University of Augsburg. During his study he got first experiences in environmental management systems. His master thesis was about a fuel switch program in Brazil as a CDM project. Based in Brazil he has been working for TÜV SÜD as a GHG auditor on freelance basis since March 2005.

Sandro Marostica is a Food Engineer with an MBA from IMD, Lausanne Switzerland. He has acquired his first experiences in the CDM market in 2004 through the creation of his broker dealer company in the UK to negotiate CER forward contracts from CDM projects in Brazil. Based in Brazil he has been working for TÜV SÜD since April 06 as General Manager and GHG auditor, and is familiar with local laws and regulations.

In order to have an internal quality control of the project, a team of the following persons has been composed by the certification body “climate and energy”:

Javier Castro (Head of Certification Body, GHG lead auditor)

1.3 GHG Project Description

This project proposes to apply to multiple swine Confined Animal Feeding Operations (located in Mato Grosso do Sul, Mato Grosso, Parana, Rio Grande do Sul, and Santa Catarina, Brazil) a GHG mitigation methodology which is applicable to intensive livestock operations. The proposed project activities will mitigate AWMS GHG emissions in an economically sustainable manner, and will result in other environmental benefits, such as improved water quality and reduced odor. The project proposes to move the designated farms from a high-GHG AWMS practice; an open air lagoon, to a lower-GHG AWMS practice; an ambient temperature anaerobic digester with the capture and combustion of the resulting biogas. The concluding purpose of this project is to mitigate animal effluent related GHG by improving AWMS practices. In total 7 farms with 7 sites are contracted in the States of Mato Grosso do Sul, Mato Grosso, Parana, Rio Grande do Sul, and Santa Catarina, Brazil.

Project participant is AgCert Do Brasil Solucoes Ambientais Ltda. Host Party of the project activity is Brazil.

The category of the project activity is in Scope 13 - Waste Handling and Disposal, and Scope 10 – Agriculture. The approved and applied baseline and monitoring methodology is Type III, Other Project Activities, Category III.D Methane recovery in agricultural and agro industrial activities for small scale project activities, version 11. According to the PDD and involved parties the start-

ing date of the project activity is June 13, 2005. The crediting period is committed as a 7 years renewable crediting period and it starts on 01/11/2007.

2 METHODOLOGY

The validation of the project consists of the following three phases:

Desk review

Follow-up interviews

Resolution of clarification and corrective action requests

In order to ensure transparency, a validation protocol was customized for the project, according to the Validation and Verification Manual. The protocol shows, in a transparent manner, criteria (requirements), means of verification and the results from validating the identified criteria. The validation protocol serves the following purposes:

It organizes details and clarifies the requirements a CDM project is expected to meet;

It ensures a transparent validation process where the validator will document how a particular requirement has been validated and the result of the validation.

The validation protocol consists of three tables. The different columns in these tables are described in Figure 1.

The completed validation protocol is enclosed in Annex 1 to this report.

Validation Protocol Table 1: Mandatory Requirements			
Requirement	Reference	Conclusion	Cross reference
The requirements the project must meet.	Gives reference to the legislation or agreement where the requirement is found.	This is either acceptable based on evidence provided (OK), or a Corrective Action Request (CAR) of risk or non-compliance with stated requirements. The corrective action requests are numbered and presented to the client in the Validation report.	Used to refer to the relevant checklist questions in Table 2 to show how the specific requirement is validated. This is to ensure a transparent Validation process.

Validation Protocol Table 2: Requirement checklist				
Checklist Question	Reference	Means of verification (MoV)	Comment	Draft and/or Final Conclusion
The various requirements in Table 1 are linked to	Gives reference to documents	Explains how conformance with the check-	The section is used to elaborate and dis-	This is either acceptable based on evidence provided

checklist questions the project should meet. The checklist is organised in seven different sections. Each section is then further subdivided. The lowest level constitutes a checklist question.	where the answer to the checklist question or item is found.	list question is investigated. Examples of means of verification are document review (DR) or interview (I). N/A means not applicable.	cuss the checklist question and/or the conformance to the question. It is further used to explain the conclusions reached.	(OK), or a Corrective Action Request (CAR) due to non-compliance with the checklist question (See below). Clarification is used when the validation team has identified a need for further clarification.
--	--	---	--	---

Validation Protocol Table 3: Resolution of Corrective Action and Clarification Requests			
Draft report clarifications and corrective action requests	Ref. to checklist question in table 2	Summary of project owner response	Validation conclusion
If the conclusions from the draft Validation are either a Corrective Action Request or a Clarification Request, these should be listed in this section.	Reference to the checklist question number in Table 2 where the Corrective Action Request or Clarification Request is explained.	The responses given by the Client or other project participants during the communications with the validation team should be summarized in this section.	This section should summarize the validation team's responses and final conclusions. The conclusions should also be included in Table 2, under "Final Conclusion".

Figure 1 Validation Protocol Tables

2.1 Review of Documents

The project design document submitted by the client and additional background documents related to the project design and baseline were reviewed. The audit team has been provided with the first PDD-version issued on January 23, 2007 which had been made public on www.netinform.de. The project design document was assessed by some revisions addressing Corrective and Clarification Requests issued by TÜV SÜD. The final updated PDD version 3 issued on May 23, 2007 serves as the basis for the assessment presented herewith.

2.2 Follow-up Interviews

TÜV SÜD performed interviews, see ref. 1 (Information Reference List), with project stakeholders to confirm selected information and to resolve issues identified in the document review. Representatives of the farms and AgCert Do Brasil Solucoes Ambientais Ltda were interviewed. The main topics of the interviews are summarized in Table 1.

Table 1 Interview topics

Interviewed organization	Interview topics
--------------------------	------------------

Representatives of the farms	Project design Technical equipment Sustainable development issues Additionality Crediting period Monitoring plan Management system Environmental impacts Stakeholder process
AgCert Brasil	Project design Technical equipment Sustainable development issues Baseline determination Additionality Crediting period Monitoring plan Environmental impacts Stakeholder process Approval by the host country

2.3 Resolution of Clarification and Corrective Action Requests

The objective of this phase of the validation was to resolve the requests for corrective actions and clarification and any other outstanding issues which needed to be clarified for TÜV SÜD's positive conclusion on the project design. The Corrective Action Requests (CAR) and Clarification Requests (CR) raised by TÜV SÜD were resolved during communications between the Client and TÜV SÜD. To guarantee the transparency of the validation process, the concerns raised and responses that have been given are summarized in chapter 3 below and documented in more detail in the validation protocol in Annex 1.

The validation is not meant to provide any consulting towards the client. However, stated requests for clarifications and/or corrective actions may provide input for improvement of the project design.

3 VALIDATION FINDINGS

In the following sections the findings of the validation are stated. The validation findings for each validation subject are presented as follows:

The findings from the desk review of the project design documents and the findings from interviews during the follow up visit are summarized. A more detailed record of these findings can be found in the Validation Protocol in Annex 1.

Where TÜV SÜD had identified issues that needed clarification or that represented a risk to fulfil project objectives, a Clarification Request or Corrective Action Request, respectively, have been issued. The Clarification and Corrective Action Requests are stated, where applicable, in the following sections and are further documented in the Validation Protocol in Annex 1. The validation of the project resulted in thirteen Corrective Action Requests and six Clarification Requests.

Where Clarification or Corrective Action Requests have been issued, the exchanges between the Client and TÜV SÜD to resolve these Clarification or Corrective Action Requests is summarized.

The final conclusions for validation subject are presented.

The validation findings relate to the project design as documented and described in the final project design documentation.

3.1 General Description of Project Activity

3.1.1 Discussion

The project participant is AgCert Do Brasil Solucoes Ambientais Ltda. The project is developed by AgCert International, Ireland. Brazil as the host Party meets all relevant participation requirements.

The objective of the project "AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil" is to apply to the farm GHG mitigation measures which will mitigate GHG emissions in an economically sustainable manner. The project foresees to replace the open air lagoons by positive pressure covered lagoon cells, creating ambient temperature anaerobic digesters.

The project design does reflect current good practice. The design has been professionally developed. A validation of the compatibility of the single components carried out by the project developer resulted in a positive conclusion. The project does moreover apply state of the art equipment.

The project boundaries are clearly defined. The project initially bundled 7 farms with installations of digesters at 7 sites being contracted in the States of Mato Grosso do Sul, Mato Grosso, Parana, Rio Grande do Sul, and Santa Catarina, Brazil. During this assessment TÜV SÜD contacted and visited 6 sites indicated in the Information Reference List. During the validation process the project participant decided to take out Fazenda Sao Marcos from the PDD. Finally, the project bundles 6 farms with installations of digesters at 6 sites. As the project participant is op-



erating/developing several similar CDM projects in the same or neighboring region, the validation process has shown that no farm of this project is included in any other existing PDD.

The project equipment can be expected to run for the whole project period and it can not be expected that it will be replaced by more efficient technologies.

Initial training and maintenance efforts are required. In the PDD and during the visit on site the project developer confirmed that such training has taken place and/or is envisaged. Documentation on executed and/or planned training activities has been submitted.

The project is currently in line with the relevant legislation and plans in the host country. The required environmental licenses are valid and have been submitted to the validation team.

The project is considered to be in line with the sustainable development policies of Brazil as improvements to manure management as well as energy supply are relevant issues in the national Brazilian policy. The final Letter of Approval by the Brazilian DNA will confirm the opinion of the DOE.

It can be expected that the project will create additional environmental benefits by reducing emissions of Volatile Organics Compounds (VOCs). The project does moreover improve the quality of the fertilizer produced as a by-product to the farming activities.

The funding for the project does not lead to a diversion of official development assistance, as according to the information obtained by the audit team, ODA does not contribute to the financing of the project.

The project starting date and the operational lifetime are clearly defined. The crediting period is clearly defined.

3.1.2 Findings

Corrective Action Request 1:

The project includes a farm from the State of Mato Grosso, why is it not mentioned in the title?

Answer:

The State of Mato Grosso is included in the whole PDD description. It was a Project Participant's decision not to have that in the Project's Title.

Corrective Action Request 2:

Site Sitio Alto do Ceu appears with a different name in the environmental license. It is requested that the name is changed excluding 'Itapora' from the name in the PDD in order to match environmental license.

Answer:

PDD has been Updated. "Itaporã" has been removed from the name in the PDD.

Corrective Action Request 4:

At Fazenda Erno Roberto Binsfeld the biodigester construction will be only finished in probably May 2007. This information should be adjusted in the PDD.

Answer:

The estimated construction completion date for “Fazenda Erno Roberto Binsfeld” has been adjusted in the site description to 30-May-2007.

Clarification request 1:

An evidence of the date when a solids separator has been disactivated at site F. Buritis is requested.

Answer:

No solid separation is performed. Declaration is available at the portal.

Email 30.05.2007:

Declaration was sent to validation team saying that solid separator was deactivated in November 2000.

Clarification request 2:

The number of biodigester modules and its size should be mentioned in the PDD.

Answer:

Number and size of biodigester modules are mentioned in the last submitted PDD.

ID 10801 - Jucelia 2: 2 cells: 38 X 12 X 5

ID 10802 - Jucelia 1: 1 cell: 28 X 10 X 5

ID 21452 - Granja Enori Pelizza: 1 cell: 30 X 12 X 5

ID 2008022 - Fazenda Buritis: 1 cell: 70 X 20 X 5

ID 26172 - Sitio Alto do Ceu: 1 cell: 41 X 13 X 5

ID 29525 - Faz. Erno Roberto Binsfeld: 1 Cell: 56 X 17 X 3.5

Clarification Request 3:

Schedule for implementation of biodigester and training for Site Faz. Sao Marcos is requested.

Answer:

Faz. São Marcos has been taken out of the PDD. Updated PDD is available at the portal.

3.1.3 Conclusion

All Corrective Action Requests and Clarification Requests are considered to be reasonably resolved. In order to avoid cases of debundling, AgCert will monitor the locations and the distances between them by using “Google Earth”.

The project is according to UNFCCC-SSC regulations.

3.2 Baseline Methodology

3.2.1 Discussion

The project is based on the approved methodology: "Type III, Other Project Activities, Category III.D., Methane recovery in agricultural and agro industrial activities for small-scale projects, version 11". The methodology has been approved by the CDM Executive Board. The selected methodology has been designed for this project and hence the project is part of the methodology on which it is built upon. Therefore the respective baseline methodology is deemed to be the most applicable one for this project. The PDD responds convincingly to each of the applicability criteria which are outlined in the baseline methodology.

The application of the methodology and the discussion and determination of the baseline are transparent. The application follows exactly each of the steps outlined in the methodology and answers the corresponding sections in a proper manner.

The baseline is determined using reliable assumptions. The parameter "population" as one of the decisive parameters for the quantitative prognosis is determined by using reliable data and is moreover based on data obtained from a year period in the past. In case of planned expansions at farm site it has been considered in the PDD. During the visit on site the availability of such comprehensive data could be observed predominantly. Hence plausible data has been provided from traceable sources ensuring the reliability of the parameter.

The baseline has been based on project specific data and does sufficiently take into account policies and developments regarding legal, economic and social issues. There is no legal requirement to capture and combust greenhouse gases produced by swine manure in AWMS. There is currently also no planned legislation that is directed towards the emission of GHG as related to AWMS. The open air lagoon is hence considered the common AWMS practice in Brazil.

The project demonstrates via the description of barriers that it is not the baseline scenario. Each step of the respective section of the methodology has hereby been applied in a correct manner. The elaborations in the PDD got substantiated by an external expert review. Concluding it has been made clear that the continuation of the AWMS by operating open air lagoons would be the most attractive course of action and hence the baseline scenario. During the visit on site the project owner substantiated these arguments by describing the financial result of the operations in the last two years.

The economic performance, the legal constraints and the common practice have been identified as potential risks to the baseline. The subsequent evaluation resulted in the assessment that no major risks to the baseline exist. This assessment is considered as being plausible.

References have been made to all data sources used.

3.2.2 Findings

Corrective Action Request 3:

Number of heads cannot be audited neither confirmed in the sites Sitio Alto do Ceu and Fazenda Buritis, due to change of software, missing data or not appropriated management of periods.



The validation team requests a report showing that the number of heads on the PDD can be confirmed in each farm system and can be easily re-produced. Alternatively the number of heads on the PDD could be changed to match a period when data is reliable and retraceable on each farm system.

Answer:

Inventories for both sites are available at the portal.

Corrective Action Request 6:

At site Faz. Sao Marcos, the number of barns should be corrected to 11, and the number of lagoons should be corrected to 4.

Answer:

Faz. São Marcos has been taken out of the PDD. Updated PDD is available at the portal.

Corrective Action Request 7:

At site Faz. Buritis, the number of lagoons should be corrected to 6, one of which is smaller circular (10x2,8)

Answer:

PDD has been updated with more up-to-date information.

Corrective Action Request 8:

At site Fax. Alto do Ceu, the number of lagoons should be corrected to 3, the 3rd one with dimensions (14x30x4)

Answer:

PDD has been updated with more up-to-date information.

Corrective Action Request 9:

At site Sao Marcos, the contact person should be changed to Ademir Batelo, as PDD contact person no longer works for the farm.

Answer:

Faz. São Marcos has been taken out of the PDD. Updated PDD is available at the portal.

Corrective Action Request 10:

At Fazenda Erno Roberto Binsfeld the validation team has identified that from October 2005 until January 2006 gilts and sows has not been mentioned separately but been indicated together in the PDD. However, on-site separate numbers for gilts and sows were available. Besides, the sow number in February 2006 and the finisher number in July 2006 is slightly different found on-site to the number given in the PDD. The following numbers have been identified on-site and should be adjusted to be conservative:

- Oct. 2005 gilts 63, sows 445
- Nov. 2005 gilts 48, sows 439
- Dez. 2005 gilts 55, sows 434

- Jan. 2006 gilts 56, sows 434
- Feb. 2006: sows 426
- July 2006: finisher: 2176

Answer:

PDD has been updated as requested.

Clarification Request 4:

-For site Faz. Sao Marcos, the owner's growth letter does not match PDD, as only the number of one type of animal is said to grow in the letter. Please clarify growth calculations.

-For site Granja Jucelia, Site I it should be submitted a growth letter to the validation team. Besides, the growth calculation in the PDD does not seem logical to the validation team. Although there is no growth indicated for some years, the baseline emissions increase. Growth plan for Granja Jucelia, Site I has to be revised.

Answer:

Faz. São Marcos has been taken out of the PDD.

For site Granja Jucelia, Site I: There is a growth letter available at the portal. PDD has been updated.

Clarification Request 5:

For site Granja Jucelia, Site I there was not submitted any evidence about the used genetics. Such a evidence should be still presented to the validation team.

Answer:

Requested document is available at the portal.

3.2.3 Conclusion

It has been used the most updated version of the methodology, namely version 11. The baseline data, mainly population data, have been verified and are correct. The Corrective Action Requests and the Clarification Requests are considered to be resolved.

Concluding it can be stated that it has been made plausible that the chosen baseline scenario is the one deemed most realistic under the given frame conditions.

The project is according to UNFCCC-SSC regulations.

3.3 Duration of the Project / Crediting Period

3.3.1 Discussion

Both the starting date of the project activity and the crediting period are clearly determined as well as the lifetime of the project activity and the length of the renewable crediting period of 7 years.

3.3.2 Findings

None

3.3.3 Conclusion

The project is according to UNFCCC-SSC regulations.

3.4 Monitoring Plan

3.4.1 Discussion

The project is based on the approved monitoring methodology "Type III, Other Project Activities, Category III.D., Methane recovery in agricultural and agro industrial for small-scale projects, version 11". The methodology has been approved by the CDM Executive Board.

The selected methodology has been designed for this project and hence the project is part of the methodology it is build upon. Therefore the respective monitoring methodology is deemed to be the most applicable one for this project. The PDD responds convincingly to each of the applicability criteria which are outlined in the monitoring methodology.

Details of the methodology as parameters to be obtained, recording frequency and archiving methods are considered being reasonable and appropriate.

The methodology and its application are described in detail and in a transparent manner. During the visit on site the implementation of the operations and maintenance manual and the data management system in order to ensure a proper implementation of the monitoring plan could be evidenced.

The monitoring plan does include all relevant parameters to determine baseline and project emissions and it is possible to monitor and/or measure the currently specified GHG indicators. The indicators which are not measured can be obtained from IPCC documents. The parameters defined allow calculating the baseline and projecting emissions in a proper manner.

According to the methodology no leakage calculation is required.

The project is considered to have no negative environmental, social and economic effects and a monitoring of such data is also not required by the applied monitoring methodology. This approach is deemed sufficient.

The PDD in combination with the Operations and Maintenance Manual does clearly indicate the authority and responsibilities within the given project structure. During the visit on site it has been described in detail how the respective organizational structure is already implemented and/ or planned. During the visit on site the validation team moreover realized that the project owner is well aware of the tasks and responsibilities.

The overall management responsibility is with AgCert International, Ireland. The company operates also trained staff in Brazil. The farm owner or representatives supports the AgCert staff during the on site audits and carries out the daily supervision of the project components and their performance. The responsibilities for each task are clearly defined and allocated to the Farm owners, AgCert and the service providers.



The quality and environmental management system (QMS and EMS), currently under implementation within AgCert, will help to support the project participants in operating the respective organizational structure.

3.4.2 Findings

Corrective Active Request 5:

Installed Flow meters should be calibrated and sealed. Certificate of calibration and seal should be presented to the validation team.

Answer:

This issue is being monthly controlled by monitoring team in monitoring documents and these documents are provided to Verification Team as request.

This issue has already been pointed out by Verification auditors and we have been working in order to accomplish with all requests.

3.4.3 Conclusion

The QA/QC manual for all involved staff and their responsibility regarding monitoring is ruled sufficiently. Signed contracts are submitted to the validation team.

The validation team can not identify any risks due to inadequate management structure or quality assurance. The above mentioned requests are answered sufficiently.

Regarding Corrective Action Request 5 on calibration the answer is acceptable at the early stage of the project; it can be expected that the certificate of calibration will be presented to the verification team. The estimations of the validated emission reductions are based on a defined flare efficiency of 98 % methane destruction as considered as well in the calculation tool. It is highlighted that

- this estimate is based on the installation of an enclosed flare, and that
- an independent third party will verify achieved efficiency testing on a sample basis as defined in the monitoring plan of the PDD.

The project is according to UNFCCC-SSC regulations.

3.5 Calculation of GHG Emissions by Source

3.5.1 Discussion

The project spatial boundaries are clearly described and limited to the farm site. An exact and correct description of the project boundaries is included in chapter B.4 of the PDD. The projects components are clearly defined in the PDD and described in figure B1 of the PDD. During the visit on site the given information has been confirmed.

Details of direct and indirect emissions are discussed in the PDD in an appropriate manner. All aspects are covered by the current approach. All methane (CH₄) emissions have been considered.

The calculations resulting in the final numbers have been submitted. The formulae used are correctly applied. Since most estimates are derived from accepted international sources, it seems reasonable to assume that they are accurate. The approach is deemed sufficient.

A leakage calculation is not necessary according to the methodology.

Concluding it can be stated that the project will reduce CO₂ emissions compared to the baseline scenario by 114,788 tonnes CO₂e over a crediting period of seven years, resulting in a calculated annual average of 16,398 tonnes CO₂ over a crediting period of seven years.

3.5.2 Findings

None

3.5.3. Conclusion

The calculation of GHG emissions and used data are according to applied methodology and its requirements.

3.6 Environmental Impacts

3.6.1 Discussion

The environmental impacts can be seen as being low. These low impacts have been sufficiently described in the PDD.

The legislation does not require an EIA for this type of project. But an environmental license for the sites is necessary. This requirement for approval has been fulfilled.

Negative environmental effects are not expected to be created by the project. Given the nature of the project design this seems to be reasonable.

Transboundary effects are not expected as the project site is far from the national boundary.

As no significant environmental impacts are expected, such impacts have not influenced the project design.

3.6.2 Findings

Corrective Action Request 11:

The name at Environmental License for site Faz. Buritis (Buriti III in the license) is not matching PDD. Please correct PDD name or provide right environmental license for the site.

Answer:

EL protocol for Fazenda Buritis is available at the portal.

Corrective Action Request 12:

Protocol of site Faz. Alto do Ceu has expired. Please provide a valid environmental licence or a protocol evidencing the request for a renewal of the environmental licence.

Answer:

Letter from Environmental Licence Department has been provided. Available at the portal.

Corrective Action Request 13:

Environmental licence of Granja Jucelia 2 has expired. Please provide a valid environmental licence or a protocol evidencing the request for a renewal of the environmental licence.

Answer:

A new protocol has been provided. Protocol has been submitted to the validation team and is also available at the portal.

Clarification Request 6:

Site S. Marcos has a protocol only for the installation licence. Please inform timeline to obtain operational license or protocol.

Answer:

Faz. São Marcos has been taken out of the PDD.

3.6.3 Conclusion

The project does comply with the environmental requirements. All environmental licences respectively environmental protocols have been submitted to the validation team.

The project is according to UNFCCC-SSC regulations.

3.7 Comments by Local Stakeholders

3.7.1 Discussion

A formal consultation process with local stakeholders has taken place and corresponding information has been submitted to the audit team. The stakeholders consulted included people from the local community and also the representatives of the local communities and the states. In addition neighbours to the site have been interviewed.

The stakeholders have been invited to meetings via post and electronic mail and which has also been published in local and regional newspapers.

Stakeholder process is required according to national legislation.

The comments to the project design have been recorded and provided. As all comments have been positive, the project design has not been changed due to stakeholder comments.

3.7.2 Findings

None

3.7.3 Conclusion

The Comments of the stakeholders were without exception positive. The project does comply with the requirements.

4 COMMENTS BY PARTIES, STAKEHOLDERS AND NGOS

TÜV SÜD published the project documents on its website from January 31, 2007 until March 01, 2007 and invited comments within 30 days, by Parties, stakeholders and non-governmental organizations.

Published:

http://www.netinform.de/KE/Wegweiser/Guide2_1.aspx?ID=2560&Ebene1_ID=26&Ebene2_ID=762&mode=1

During the commenting period there have been no comments received.

5 VALIDATION OPINION

The Certification Body "Climate and Energy" has been ordered by AgCert International PLC, Ireland (AgCert International) to validate the project AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil.

By avoiding GHG emissions from open air lagoons, the project results in reductions of GHG emissions that are real, measurable and give long-term benefits to the mitigation of climate change. An analysis of the investment, technological and legal barriers demonstrates that the proposed project activity is not a likely baseline scenario. Emission reductions attributable to the project are hence additional to any that would occur in the absence of the project activity. Given that the project is implemented as designed, the project is likely to achieve the estimated amount of emission reductions.

Additionally the assessment team reviewed the estimation of the projected emission reductions. TÜV SÜD confirms that the indicated amount of emission reductions of 114,788 tonnes CO_{2e} over a crediting period of seven years, resulting in a calculated annual average of 16,398 tonnes CO_{2e} represents a reasonable estimation using the assumptions given by the project documents.

It is opinion of TÜV SÜD that the project as described in the final project design document issued on May 23, 2007, meets all relevant UNFCCC requirements for the CDM, set by the Kyoto Protocol, the Marrakech Accords and relevant guidance by the CDM Executive Board; furthermore that the project meets all relevant host country criteria and correctly applies the baseline and monitoring methodology "Type III, Other Project Activities, Category III.D., Methane recovery in agricultural and agro industrial for small-scale projects, version 11.

Hence, TÜV SÜD will recommend the project for registration as CDM project activity by the CDM Executive Board.

Prior to the submission of this validation report to the CDM Executive Board, TÜV SÜD will have to receive the written approval of the DNA of involved parties, including confirmation by the DNA of Brazil that the project assists in achieving sustainable development.

The validation is based on the information made available to us and the engagement conditions detailed in this report. The validation has been performed using a risk based approach as described above. The only purpose of this report is its use during the registration process as part of the CDM project cycle. Hence, TÜV SÜD can not be held liable by any party for decisions made or not made based on the validation opinion, which will go beyond that purpose.

Munich, 3.6.2007

Munich, 3.6.2007



Werner Betzenbichler

Head certification body
"climate and energy"



Markus Knödseder

Project Manager

Document: Validation Report BR07-S-31_01062007

Validation of the AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil



Annex 1: Validation Protocol

Document: Validation Report BR07-S-31_01062007

Validation of the AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil



Annex 2: Information Reference List

Document: Validation Report BR07-S-31_01062007

Validation of the AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil



Document: Validation Report BR07-S-31_01062007

Validation of the AWMS Methane Recovery Project BR07-S-31, Mato Grosso do Sul, Parana, Rio Grande do Sul, and Santa Catarina, Brazil



Industrie Service